# Sectional CIPP of Sanitary Sewer Force Main Preserves Historic Hull Waterfront

Charles Tripp, P.E. Project Manager

November 16, 2017





#### History of Hull


- The Town of Hull, MA is a suburban ocean-side community of roughly 11,000 people located on a peninsula just south of Boston Harbor
- Favorite seasonal and year-round community for it three-milelong sandy beach on the Atlantic Ocean
- C Having a land area of only 2.5 square miles, 99 percent of the Town is connected to the municipal sewer system which dates to 1860
- Due to long travel times in interceptors, and several force mains these pipe systems are prone to deterioration due to hydrogen sulfide attack

- Focus of Project
  - Nantasket Avenue forced main 1974
    - 14" ductile iron force main
    - C 4,700 linear feet
    - From P.S. #3 to discharge at 30" RCP sewer
    - Conveys significant portion of Town's flow to Hull WWTF
  - C P.S. #3
    - Pump capacities = 1700 GPM
    - Pump operating flows = 240 GPM
      - Flow velocity = 0.75 ft/sec
      - Not sufficient flushing velocity










- Investigation
  - Sewer Operator decides to temporarily shut down P.S. #3 and CCTV inspect forced main
    - Spurred by December 2015 sewer failures in Plymouth, MA



30" steel pipe deteriorated due to H<sub>2</sub>S corrosion resulting from low buildout and low flow velocity.

- Investigation
  - In 2002, Town extends 14" DI forced main 45 LF down existing 30" RCP sewer and abandons existing valve manhole
  - CIPP line downstream sewer, and line discharge manhole



- Investigation
  - In June 2016, Town CCTV inspects 14" DI force main from discharge manhole over length of 45 LF extension
  - C Downstream-most 15 LF are found to be deteriorated from H<sub>2</sub>S corrosion



#### Issues


- Newly Paved Intersection at Bay Street
  - Under MassDOT moratorium



#### Issues

#### C Access

 Only discharge manhole at Bay Street intersection is available for access to complete work



#### Repair Alternatives Discussed

- Spin-Cast Pipe Lining Repair
  - Was not believed to be viable, as it would be tough to seal voids between DI pipe and RCP host pipe outside of DI



#### Repair Alternatives Discussed

- Spin-Lining Repair
  - Was not believed to be viable since only one point of access was available, and it would be difficult to seal the annular space




## Repair Alternatives Discussed


- Sectional CIPP Repair
  - C Typically requires two points of access, but in relatively short distances, can be performed with one point of access



## Repair Design

- Sectional CIPP Repair
  - Repair 15 LF from downstream manhole location using Sectional CIPP repair
  - C Replace DI drop leg with 15" PVC





## Repair Design

#### Temporary Bypass Pumping

- Town decides to avoid time and costs associated with setting up temporary bypass pumping around location of repair
- Sewer Operator contracts with septic hauler over estimated three nights of work

#### Working Hours

C Flow data at PS #3 indicated that from 11:00 PM to 7:00 AM was best time

#### Public Notice


 Town uses letter boards and mailers to local residents for notification prior to construction

#### Police Detail Coverage

Costs covered by the Town

#### **Emergency Bid Waiver**

- Time Was of the Essence
  - Town wanted to forego the traditional bid process, due to situation found via CCTV inspection
  - A waiver was requested from DCAMM to obtain 3 quotes from appropriate vendors in lieu of public bid
  - Waiver was granted!



#### **Contract Award**

- **Summary** 
  - C DCAMM waiver received on July 18, 2016
  - Three quotes were requested
  - Two Bids Received
  - C Awarded to Low Bid on August 1, 2016













Before After







#### Outcomes

- Project Summary
  - Bid Date: August 1, 2016
  - C Award Date: August 3, 2016
  - Construction Period: August 30-31, 2016
  - Sectional CIPP Repair Cost (~14LF): \$14,130
  - Status: Success!

## Continued Proactive Efforts by Town in 2017

- C Discharge Piping at Pump Station #3 has been replaced to include an isolation valve, new fittings, and a "wye" connection for launching of internal inspection technologies.
- Town contracts to perform test-pits over 4,625 LF length of entire force main to perform soil corrosivity testing, and pipe thickness testing.
- Sectional CIPP repair re-inspected by Town Sewer Operator in July 2017 to confirm integrity



## **Questions & Discussions**

